

* Construction Notice *



Dear Customers,

We apologize for the noise that you are experiencing as a result of the new well construction and water plant expansion. In order to meet future water demand, a 4th well is being drilled. Every effort is being made to reduce the noise levels. A tentative work schedule is attached and updates will be made on www.municipaldistrictservices.com/notices

- WHO:** Harris County Municipal Utility District No. 387
Pate Engineers, Inc., Engineers for the District (713)462-3178
Project Contacts:
Fred Le Blanc- Project Manager- The Woodlands Development Co. (281)719-6121
Chad Abram- District Engineer -Pate Engineers, Inc.
(713)462-3178
- WHAT:** Water Plant Capacity Expansion and Well Drilling
- WHEN:** February 2012 (Well Drilling) through December 2012
- WHERE:** Harris County Municipal Utility District No. 387 Water Plant No. 2 on North Heritage Mill Circle
- WHY:** As part of the Water Plant Expansion project, a second well will be drilled, along with construction of a second ground storage tank, pumps and pressure tank. This is to supply the growth in Creekside Park because Harris County MUD 387 produces the water that Harris-Montgomery Counties MUD 386 supplies to the Creekside Park customers.

WHAT DOES THIS MEAN?

While we expect inconveniences to be minimal, we certainly sympathize with any inconveniences that might arise. *We do not anticipate any water pressure issues, but there may be a few days of lower-than-usual water pressure. Please do not be alarmed.* We hope that there is understanding regarding the necessity of the project, and realization that it will be temporary.

SHOULD YOU HAVE ANY PROBLEMS WITH YOUR WATER SERVICE, PLEASE CONTACT MUNICIPAL DISTRICT SERVICES DIRECTLY

AT (281)290-6503.

THIS NUMBER IS ANSWERED 24 HOURS A DAY.

Well Drilling Tentative Work Schedule

<u>Date</u>	<u>Time</u>	<u>Work Description</u>	<u>Noise Level</u>
03/05/12 – 03/07/12 Mon. – Wed.	24-Hour Operation	Ream, set & cement casing - Mud system will be operating.	High
03/08/12 – 03/09/12 Mon. – Fri.	6:30 a.m. – 6:30 p.m. Days Only	Prepare to under-ream	Moderate
03/12/12 – 03/15/12 Mon. – Wed.	24-Hour Operation	Under-ream & set screens - Mud system will be operating.	High
03/15/12 – 03/16/12 Thur. – Fri.	24-Hour Operation	Airlift development - No mud system operation – noise should not be very high.	Low to Moderate
03/17/12 – 03/19/12 Sat. – Mon. Morning	6:30 a.m. – 6:30 p.m. Days Only if needed.	Probably no work – if there is work it will only be during the day.	Little to None
03/19/12 – 03/23/12 Mon. – Fri.	6:30 a.m. – 6:30 p.m. Days Only	Demobilize drilling equipment & mobilize test pump.	Low
03/26/12 – 04/13/12	24-Hour Operation - No night work on weekends.	Develop with test pump. We will try to limit nighttime noise as much as possible.	Moderate to High
04/16/12 – 04/20/12 Mon. morn. – Fri. morn.	24-Hour Operation	Pump test the well.	Moderate to High

When we run the pump test the pumping equipment has to run at night for several days.

END OF NIGHT WORK REQUIREMENTS FOR THE WATER WELL CONSTRUCTION.